MATJHABENG

Municipality Umasipala P/ O Box 708 Welkom, 9460 South Africa



Mmasepala Munisipaliteit Tel: (057)916 4060 Fax: 086 536 0906

E-mail: nokwanda.xamesi@matjhabeng.co.za

To

MUNICIPAL MANAGER

From:

EXECUTIVE DIRECTOR INFRASTUCTURE

Date:

25 JANUARY 2019

SUBMISSION

1. PURPOSE

The purpose of the submission is to assist Vukuphile Learner Contractors who underpriced on their tender documents regarding the connection of water meters, house connections and water network in Thabong Extension 20 (Hani Park).

2. BACKGROUND

The extension of a water network, house connections and 180 water meters in Thabong Extension 20 (Hani Park) project is currently being implemented by the Municipality through MIG funding. This project entails the extension of a water network, house connections and the installation of 180 water meters in Thabong Ext.20. The project was awarded to Kalosi Trading Projects, a vukuphile contractor and is being managed by Epitome Consulting Engineers. A request to assist the learner contractors in revising their rates was received from Epitome Consulting Engineers and is attached for ease of reference.

3. DISCUSSION

After Kalosi Trading Projects was appointed, the Consultant noticed many errors on the priced tender documents. Most crucial items were underpriced thus posing a challenge on the contractor to successfully complete the project. The priced tender documents currently reflect a financial loss for the contractor and presents a challenge to deliver quality service for the community of Thabong Extension 20 (Hani Park). Before construction proceeds any further, it is recommended that the rates are adjusted in order to ensure successful completion of the project and adequate service delivery.

It is therefore proposed that the awarded contract amounts are amended to suit the recommendation made by the consultant. The new contract amount shall be R2 336 967.76 thus additional funding of R394 170.87 is needed.

4. FINANCIAL IMPLICATIONS

| A | SUMMARY OF SECTIONS | APPOINTED AMOUNT | PROPOSED CONTRACT AMOUNT | ADDITITIONAL AMOUNT NEEDED |
|---|---|---------------------|--------------------------------|-------------------------------|
| В | Schedule 1: Preliminary and General | R 576 852.20 | R 687 324.00 | R 110 471.80 |
| C | Schedule 2: Hani Park X20 | R 1 189 326.79 | R 1 437 192.14 | R 247 865.36 |
| D | Sub Total | R 1 766 178.99 | R 2 124 516.14 | R 358 337.16 |
| E | Contingencies (10%) | R 176 617.90 | R 212 451.61 | R 35 833.72 |
| F | Total Construction Budget (Vat Inclusive) | R 1 942 796.88 | R 2 336 967.76 | R 394 170.87 |

5. <u>RECOMMENDATIONS</u>

(MUNICIPAL MANAGER

It is hereby recommended as follows:

The additional required amount of **R394 170.87** be approved, therefore increasing the contract amount to **R2 336 967.76**. This adjustment will ensure that the contractor has adequate financial capacity to complete the works.

| COMPILED BY: | 25/01/2019 |
|--|--------------------|
| N.S BIYELA | DATE |
| PMU TECHNICIAN | |
| RECOMMANDED BY: | , 1 |
| | 25/01/2019. |
| SHEPHERD VHUNGA SENIOR PROJECT MANAGER | DATE |
| RECOMMENDED BY: | , , |
| VI: ATT | 06/02/3019 DATE |
| T. MAKOFANE ACTING EXECUTIVE DIRECTOR: INFRASTRUCTURE | DATE |
| | , |
| RECOMMENDED BY: | EX 02 2019 DATE |
| T. PANYANI CHIEF FINANCIAL OFFICER | DATE ' |
| APPROVEDEBY: | 0/07/2010 |
| ZHABISO TSOAELI | 08/07/2019 DATE |

3 Rose Avenue Kempton Park 1630

Tel:

+27 11 391 5049

Cell:

+27 83 404 2135

Fax:

+27 11 391 8136

Reg No: 2009/095570/23 Vat Reg No: 4560260764



Web: http://www.epitomeconsulting.co.za

B-mail: Info@epitomeconsulting.co.za

or

element@epitomeconsulting.co.za

Multi-disciplinary civil engineering consultancy and project management organisation providing services in:
Water conservation and Water Demand Management, Water and Sanitation, Roads and Stormwater, Structural Engineering,
Project and Programme Management in the South African Market.

"Making a difference where it really matters!"

Project Manager Matjhabeng Local Municipality Cnr. Ryk & Stateway Street, Civic Centre, Welkom 9460 Tel: (057)-3913911

Fax: (057)-357 4754

Date

25 January 2019

Attention:

Mr. Thabiso Tsoaeli

Dear Mr. Tsoaeli,

04/2018 A/B: EXTENSION OF THE WATER NETWORK, HOUSE CONNECTION AND 180 WATER METERS IN THABONG EXTENSION 20(HANI PARK)

The tendered prices of the contractors for the above-mentioned project are lower than the market rates. This may compromise the contractor's quality of the work on site. Since these are learner contractors from Vuk'uphile and it is important that they be assisted.

We, therefore, present our proposal on how the contractors can be assisted to complete the project and deliver services to the community and assist towards saving water for the municipality.

Yours/faithfully,

Clement Mokoenene for Epitome Consulting

"Making a difference where it really matters"

| ABS 1200 A 8.3 8.3.1 8.3.2 PSA 8.3.2.1 | Description PRELIMINARY AND GENERAL SECTION: PRELIMINARY AND GENERAL FIXED-CHARGE ITEMS Contractual Requirements Establish Pacilities on the Site: a) Facilities for Engineer b) Facilities for Contractor Offices and storage sheds Ablution and latrine facilities | Sum Sum Sum | 1 1 | 10 000.00 60 000.00 | A | 10 000.00 | Rate 24 000 00 | A | 24 000 00 | Rate 14 000.00 | R | Amount |
|---|---|---|--|--|--|---|--|---|--|--|--|--|
| ABS 1200 A 8.3 8.3.1 8.3.2 PSA 8.3.2.1 | SECTION: PRELIMINARY AND GENERAL FIXED-CHARGE ITEMS Contractual Requirements Establish Facilities on the Site: a) Facilities for Engineer b) Facilities for Contractor Offices and storage sheds | Sum | | | | 10 000.00 | 24 000 00 | | 24 090 90 | 14 000.00 | R | 14 000.00 |
| A 8.3.1 8.3.2 PSA 8.3.2.1 | FIXED-CHARGE ITEMS Contractual Requirements Establish Facilities on the Site: a) Facilities for Engineer b) Facilities for Contractor Offices and storage sheds | Sum | | | | 10 000.00 | 24 000 00 | | 24 000 00 | 14 000.00 • | R | 14 000.0 |
| 8.3.1 8.3.2 PSA 8.3.2.1 | Contractual Requirements Establish Facilities on the Site: a) Facilities for Engineer b) Facilities for Contractor Offices and storage sheds | Sum | | | | 10 000.00 | 24 000 00 | | 24 000 00 | 14 000.00 | R | 14 000.0 |
| 8.3.2 PSA 8.3.2.1 | Establish Facilities on the Site: a) Facilities for Engineer b) Facilities for Contractor Offices and storage sheds | Sum | | | | - | 2100000 | | .,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,, | | •• | |
| PSA 8.3.2.1 | a) Facilities for Engineer b) Facilities for Contractor Offices and storage sheds | | 1 | 60 000.00 | | | | | . 1 | - 1 | | |
| į | b) Facilities for Contractor Offices and storage sheds | | 1 | 60.000.00 | | 60 000.00 | 00,000 | | 60 000.00 | - | R | |
| | Offices and storage sheds | Sum | Ł | | | | 00 000,00 | | 00000.60 | | ,, | |
| | | Sum | Ì | | | | | | 10.000.00 | 2,000,00 | n | aina e |
| | Ablution and latrine facilities | [| 1 | 7 000.00 | | 7 000.00 | 10 000.00 | | 10 000 00 | 3 000,00 | R | 3 000,6 |
| | | Sum | 1 | 4 000.00 | | 4 000.00 | 10 000.00 | | 10 000.00 | 6 000.00 | R | 3,000 6 |
| | Tools and equipment | Sum | 1 | 9 000.00 | | Rate Only | 9 000.00 | | Rate Only | + | | Rate On |
| | Water supplies, electric power and communications | Sum | 1 | 2 000,00 | R | 2 000.00 | 10 000.00 | R | 10 000.00 | 00,000 | R | 8 000. |
| | Dealing with water (Subclause 5.5) | Sum | 1 | 1 000.00 | R | 1 000,00 | 10 000.00 | R | 10 000 00 | 9 000.00 | R | 9 000. |
| 8.3.3 | Other fixed-charge obligations | Sum | 1 | 15 000.00 | | Rate Only | 12 000 00 | | Rate Only | | | Rate Or |
| 8.4 | TIME-RELATED ITEMS | | | | | | | | | | | |
| 8.4.1 | Contractual Requirements | Minu | 6 | 10 000.00 | | 60 000.00 | 10 000 00 | | 60 000.00 | , | | |
| 8,4,2 | Operate and maintain facilities on the Site: | | | | | | | | | | | |
| PSA 8.4.2.1 | a) Facilities for Engineer | Mnt | 6 | 10 000.00 | R | 60.000.00 | 10 000.00 | R | 60 000.00 | | 18 | |
| 8.4.2.2 | b) Facilities for Contractor for duration of construction, except where otherwise stated | | | | | | | | | , | | |
| 8.4.2.2.1 | Offices and storage sheds | Mnti | 6 | 7 000,00 | R | 42 000.00 | 7 000.00 | R | 42 000.00 | - | Ř | |
| 8,4.2.2.2 | Ablution and latrine facilities | Mnti | h 6 | 4 000.00 | R | 24 000.00 | 4 000.00 | R | 24 000.00 | | R | |
| 8.4.2.2.3 | Tools and equipment | Mnt | h 6 | 9 000.00 | R | 54 000,00 | 9 000 00 | R | 54 000.00 | | R | |
| 8.4.2.2.4 | Water supplies, electric power and | Mnt | h 6 | 1 000.00 | R | 6 000.00 | 1 000,00 | R | 6 000.00 | | Ř | |
| B.4.2.2.5 | Dealing with water (Subclause 5.5) | Mnt | h 6 | 1 000.00 | | Rate Only | 1 000.00 | | Rate Only | | | Rate O |
| 8.4.2.2.6 | Access (Subclause 5.8) | Mnt | h 6 | 1 500.00 | | Rate Only | 1 500.00 | | Rate Only | / | | Rate C |
| 8,4,3 | Supervision | Mnt | h 6 | 10 000.00 |) | Rate Only | 10 000 00 | | Rate Only | , | | Rate (|
| 8.4.4 | Company and head office overhead costs | Mnt | h 6 | 6 000.00 | R | 30 000.00 | 00,000 7 | R | 30 000 00 |) : | n | |
| | | | | | | | | | | | | |
| | | | | | - | | | 1 | | | ĺ | |
| | 8.4 8.4.1 8.4.2 PSA 8.4.2.1 8.4.2.2.1 8.4.2.2.2 8.4.2.2.3 8.4.2.2.4 8.4.2.2.5 8.4.2.2.6 8.4.3 8.4.4 | communications Dealing with water (Subclause 5.5) 8.3.3 Other fixed-charge obligations 8.4 TIME-RELATED ITEMS 8.4.1 Contractual Requirements 9.4.2 Operate and maintain facilities on the Site: PSA 8.4.2.1 a) Facilities for Engineer b) Facilities for Contractor for duration of construction, except where otherwise stated 8.4.2.2.1 Offices and storage sheds 8.4.2.2.2 Abjution and latrine facilities 8.4.2.2.3 Tools and equipment 8.4.2.2.4 Water supplies, electric power and 8.4.2.2.5 Lealing with water (Subclause 5.5) 8.4.2.2.6 Access (Subclause 5.8) 8.4.3 Supervision | communications Dealing with water (Subclause 5.5) 8.3.3 Other fixed-charge obligations 8.4 TIME-RELATED ITEMS 8.4.1 Contractual Requirements 8.4.2 Operate and maintain facilities on the Site: 25A 8.4.2.1 a) Facilities for Engineer b) Facilities for Contractor for duration of construction, except where otherwise stated 8.4.2.2.1 Offices and storage sheds 8.4.2.2.2 Ablution and latrine facilities 8.4.2.2.3 Tools and equipment 8.4.2.2.4 Water supplies, electric power and 8.4.2.2.5 Dealing with water (Subclause 5.5) 8.4.2.2.6 Access (Subclause 5.8) 8.4.3 Supervision Company and head office overhead costs | communications Dealing with water (Subclause 5.5) 8.3.3 Other fixed-charge obligations Sum 1 Sum 1 | communications Dealing with water (Subclause 5.5) B.3.3 Other fixed-charge obligations Sum 1 1000.00 Sum 1 15000.00 Sum 1 15000.00 Sum 1 15000.00 Sum 1 15000.00 Math 6 10000.00 Math 6 10000.00 Sum 1 15000.00 Math 6 10000.00 Math 6 1000.00 Sum 1 15000.00 Math 6 1000.00 Math 6 1000.00 Sum 1 1 1000.00 Math 6 1000.00 Math 6 1000.00 Sum 1 1 1000.00 Math 6 1000.00 Sum 1 1 1000.00 Math 6 1000.00 Math 6 1000.00 Sum 1 1 | Dealing with water (Subclause 5.5) Sum 1 1 000.00 R | Communications Dealing with water (Subclause 5.5) Sum 1 1 000.00 Rate Only | Dealing with water (Subclause 5.5) Sum 1 1 000.00 Rate Only 15 000 00 | Dealing with water (Subclause 5.5) Sum 1 1 000.00 R 1 000.00 R | Communications Dealing with water (Subclause 5.5) Sum 1 1 000.00 R 1 000.00 R 10 000.0 | Communications Dealing with water (Subclause 5.5) Sum 1 1 000.00 R 1 000.00 R 10 000.0 | Communications Dealing with water (Subclause 5.5) Sum 1 1000.00 R 1000.00 R 10 000.00 R 10 000 00 9 000.00 R |

| ltem | Payment | Description | Unlt | Qty | Rate | Amount | Rate | Amount | Rate | | Amount 40 000,00 |
|-------|-------------|--|-------------|-----|-----------|------------|-----------|------------|----------|---|------------------|
| TOTAL | BROUGHT F | ORWARD | | | | 360 000,00 | | 400 000,00 | | | 40 900,00 |
| 1.2.5 | 8,4,5 | Other time-related obligations | Moth | 6 | 5 000.00 | Rate Only | 5 000 00 | Rate Only | | R | ate Only |
| 1.2.5 | | Payment for a Community Liaison Officers | Mnth | 6 | 5 000,00 | 30 000.00 | 5 000.00 | 30 000.00 | | R | |
| | | | Sum | 1 | 7 500,00 | 7 500.00 | 7 500.00 | 7 500 00 | | R | |
| 1,2.7 | | Nameboard | Suili | 1 | 7 300,000 | , 000.00 | 7 500.00 | . ,, | | | |
| 1.2.8 | 8.4.7 | Compliance with the Occupational Health and Safety Requirements for the duration of the contract | Sum | 1 | 15 000.00 | 15 000.00 | 18 000,00 | 18 000.00 | 3 000.00 | R | 3 000.00 |
| | 8,5 | Provesional Sums stated by the Engineer | | | | | | | | | |
| | | Scheduled fixed-charge and value-related items: | | | i | • | | | | | |
| 1.2.9 | 8.3.1 | Fixed preliminary and general charges | Sum | 1 | 10 000.00 | 10 000,00 | 10 000.00 | 10 000,00 | • | R | 1 |
| 1.3.0 | 8.3.2 | Value-related preliminary and general charges | Sum | 1 | 10 000.00 | 10 000.00 | 10 000.00 | 10 000.00 | • | R | • |
| | | Scheduled time-related items: | | | | | | | | | |
| 1.3.1 | 8,4,1 | Time-related preliminary and general charges | Sum | 1 | 20 000.00 | 20 000.00 | 20 000.00 | 20 000 00 | | R | |
| | D 2.3.2 | Training allowance paid to targeted labour in terms of formal training | Prov Sum | | 20 000.00 | 20 000,00 | 20 000 00 | 20 000.00 | - | R | - |
| | D 2.3.2 | ii) Extra-over for the administration of payment of training allowances to targeted labour (max.10%) | % | 10% | 20 000.00 | 20.00 | 20 000 00 | 20 00 | | R | |
| | 8.6 | Prime cost sums: | | | | ! : | | | | | |
| 1.3.2 | | Additional tests required by the engineer | PC Sum | 1 | 20 000.00 | 20 000.00 | 20 000.00 | 20 000.00 | - | R | • |
| 1.3.3 | | Charge required by contractor on subitem PC Sum above | 9% | 0 | 20 000.00 | 20.00 | 20 000,00 | 20.00 | | R | - |
| | 8.8.4 | Location and protection of existing services: | | | | | | | | | |
| | | Provision of detecting devices for: | | | | : | | | | | , |
| 1.3.4 | | Water and sewer pipes | Sum | 1 | 10 000.00 | 10 000.00 | 10 000.00 | 10 000,00 | ٠ . | R | |
| 1.3.5 | | Electrical and other cables | Sum | 1 | 10 000.00 | 10 000,00 | 10 000.00 | 10 000.00 | | R | • |
| | | Hand excavation necessary for locating and exposing existing services in all materials: | | | | - | | | | | |
| 1.3.6 | | In roadways | W, | 87 | 70.00 | 6 106.10 | 100,00 | 34 892.00 | 330.00 | R | 28 785.90 |
| 1.3.7 | | In all other areas | m¹ | 117 | 70.00 | 8 206.10 | 400.00 | 46 892,00 | 330.00 | R | 38 685.90 |
| | | | | | | | | | | | |
| | | | | | | | | | | | |
| 1 | | | | | | | | | | | |
| TOTA | L CARRIED I | FORWARD | | | | 526 852,20 | | 637 324.00 | | R | 110 471.80 |

| [| D | Description | Unit | OIV | Rate | Amount | Rate | Amount | Rate | | Amount |
|---------------|-------------------|---|------|-----|----------|--------------|-----------|--------------|------|---|------------|
| Item | Payment BROUGHT I | | 1 | | | 526 852.20 | | 637 324.00 | | R | 110471.80 |
| 1.3.9 | 8,9 | Compensation in terms of subsubclause 57(4)(b)(ii) for delays due to the circumstances described in subclauses 57(1) and (2) of the general conditions of contract, as amended | day | 10 | 5 000,00 | 50 000.00 | \$ 000.00 | 50 000.00 | | R | |
| TOTAL | | ORWARD TO SUMMARY | | | | R 576 852.20 | | R 687 324.00 | | R | 110 471.80 |

EXTENSION OF WATER NETWORK, HOUSE CONNECTIONS AND METERS (180 STANDS) HANI PARK

| | | | | | | SI TRADING PR | Rate | Amount | Rate | Amount |
|-------|------------------|--|----------------|------|-----------|---------------|-----------|------------|-----------|-------------|
| Item | Payment | Description | Unit | Oth | Rate | Amount | Rate | Alternic | NACE | |
| 2.10 | SABS 1200 C | SITE CLEARANCE | | | | | | | | |
| | 8.2.1 | Clear and grub | ha | 0.2 | 17 500.00 | 3 500.00 | 50 000,00 | 10 000,00 | 32 500.00 | 6 500.00 |
| 3,10 | SABS 1200 DB | EARTHWORKS (PIPE TRBNCHES) | | | | | | | | • |
| | 6.3.1 | Site Clearance | | | | - | | | | |
| | 8.3.2 | Excavation | | | | : | | | | • |
| | | (i) For trenches up to 1.5 m in depth, using labour intesive construction methods | | | | • | | | - | • |
| | | Over and up to | | | | , | | | | |
| 3.1.1 | | 0 m 1.5 m | m³ | 1395 | 65.00 | 90 675.00 | 90.00 | 125 550.00 | 25.00 | 34 875.00 |
| | | (ii) For trenches over 1.5m in depth, using conventional construction methods | | | | • | | | | |
| | | Over and up to | | | | | | | | |
| 3.1.2 | | 0m 2.0 m | m³ | 0 | 95.00 | | 95.00 | - | | • |
| | | (b) Extra-over item (a), above, for: | | | | | | | | |
| 3.1.3 | | i) Intermediate excavation | m³ | 209 | 350.00 | 73 150.00 | 200.00 | 41 800 00 | (150.00) | (31 350.00) |
| 3.1.4 | | ii) Hard rock excavation | m³ | 140 | 650.00 | 77 000.00 | 350.00 | 49 000.00 | (200.00) | (28 000.00) |
| | 8.3.3 | Excavation Ancillaries | | | | | | | | |
| | 8.3.3.1 | Make up deficiency in backfill material (provisional): | | | | | | | | • |
| 3.1.5 | | (a) from other necessary excavations on site | m³ | 150 | 200.00 | 30 000.00 | 200.00 | 30,000,00 | • | |
| 3.1.6 | | (b) by importation from commercial or off-site sources selected by the contractor | m³ | 250 | 650.00 | 162 500.00 | 650,00 | 162 500,00 | | |
| 3.2.0 | 8.3.3.3 | Compaction in road reserves | w ₃ | 628 | 120.00 | 75 369,00 | 90.00 | 56 520,00 | (30.00) | (18 840,00 |
| | PSDB 8.3.5(a) | Services that intersect a trench | | | | | Ŷ | - | * | • |
| 3,2.1 | | a) Water house connections. | No | 2 | 1 090.04 | 2 180,00 | 1 090,00 | 2 180.00 | | • |
| 3.2.2 | | b) Water pipes up to 300mm Dla. | No | 2 | 547.4 | 1 094.98 | 547.49 | 1 094.98 | | - |
| | | | | | | | | | | |
| 1 | AL CARRIED | | | _ | | 515 459.98 | | 478 644.98 | | (36 815.00 |

| item | Pavment 1 | Description | Unit | Qty | Rate | Amount | Rate | Amount | Rate | Amount |
|-------|--------------------------|--|----------------|-----|-----------|------------|--|------------|----------|-------------|
| | BROUGHT F | | | | | 515 459.98 | | 478 644,98 | | (36.815.00) |
| 3.2.3 | | c) Stormwater pipes up to 1050mm Dia. | No | 2 | 1 320,00 | 2 640.00 | 1 320.00 | 2 640,00 | | |
| 3.2.4 | | d) Sower house connections. | Νo | 2 | 1 812,50 | 3 625,00 | 1 812.50 | 3 625 00 | | |
| 3.2.5 | | e) Sewer pipes up to 300mm Dia. | No | 2 | 1 500.00 | 3 000.00 | 1 500.00 | 3 000,00 | | : |
| 3.2.6 | | f) Cables. | No | 5 | 440.00 | 2 200.00 | 440 00 | 2 200,00 | | - |
| 3.2.7 | | g) Kerbs and channels. | No | 1 | 360.00 | 360.00 | 2 340.00 | 2 340.00 | 1 980.00 | 1 980.00 |
| | PSDB 8.3.5(b) | Services that adjoin a trench | | | | | | | | |
| 3.2.8 | | a) Cables. | m | 5 | 440.00 | 2 200.00 | 440.00 | 2 200.00 | | |
| | PSDB 0.3.5(c) | Services that require special care | No | 5 | 1 650.00 | 8 250.00 | 1 800 00 | 9 000.00 | 150.00 | 750.00 |
| | PSDB 8.3.5(d) | Trees in construction path | No | 1 | 10 000.00 | 10 000.00 | 10 000 00 | 00.000 | - | , |
| | PSDB 8.3.6.1(a) | Re-instate unreinforced concrete, complete | m² | 5 | 685.00 | 3 425.00 | 686 00 | 3 425.00 | | |
| | PSDB 9.3.6.1(b) | Re-instate grass sods, complete | m² | 5 | 232.39 | 1 161.95 | 232.39 | 1 161.95 | | , |
| 3,3,0 | SANS 1200DA 8.3.10 | Top solling including trimming, filling, topsolling and levelling of verges, removal of debris, rocks, etc. using stockpiled material. | m² | 5 | 1 470.43 | 7 352.15 | 1 470 43 | 7 352.15 | , | , |
| 4,10 | SABS 1200 LB | BEDDING (PIPES) | | | | , | | | ^ | |
| | 8.2.1 | Provision of bedding from trench excavation | | | | | , | | | : |
| 4.1.1 | | (a) Selected granular material for bedding | m³ | 363 | 126.00 | 45 738.00 | 120.00 | 43 560 00 | (6.00) | (2 178.00) |
| 4.1.2 | | (b) Selected fill material | m³ | 254 | 112.00 | 28 448.00 | 90.00 | 22 860.00 | (22.00) | (5 598.00) |
| | B.2.2.1 | From other necessary excavation (Provisional) | | | | | | | - | |
| 4.1.3 | | (a) Selected granular material for bedding | m _a | 181 | 335.70 | 60 761.70 | 120.00 | 21 720.00 | (215.70) | (39 041.70) |
| 4.1.4 | | (b) Selected fill material | m³ | 127 | 36.00 | 4 572.00 | 78.00 | 9 906,00 | 42.00 | 5 334,00 |
| | 8,2.2.3 | From commercial sources (Provisional) | | | | | | | | |
| | | 1 | | | | | | | | |
| | | | | | | | | | | |
| | L CARRIED F | ONTERINO | ╂ | - | | 699 193,78 | | 623 635.08 | | (75 558,70 |

Rate Amount Item Payment Description TOTAL BROUGHT FORWARD Amount Amount Unit Qty Rate 623 635.08 699 193.78 (75 558,70) 96 630.47 1 067.74 96 630.47 1 067.74 91 (a) Selected granular material m³ 4.1.5 1 170 27 74 312.15 1 170.27 74 312.15 64 (b) Selected fill material 4,1,6 **SABS 1200** MEDIUM PRESSURE PIPELINES 5.10 L Supply, lay and bed (Class B) complete with couplings including short lengths for pipes of the following materials and diameters 0.2.1 uPVC pipes (Class 12) 40 950.00 78.00 100.00 52 500.00 525 22.00 11 550.00 n) 32mm diameter 5.1.1 7 740.00 150.00 19 350.00 90.00 11 610,00 60.00 129 5.1.2 h) 63mm dlameter 85.00 16 915.00 17 910.00 175.00 34 825,00 90,00 c) 75mm diameter m 199 5.1,3 115.00 38 295.00 44 955.00 250.00 83 250.00 333 135.00 d) 90mm diameter 5.1.4 2 400.00 300 00 4 500.00 140.00 2 100.00 160.00 15 5,1,5 e) 110mm dlameter m 310.00 197 780.00 388.32 247 748.75 78.32 49 968.75 f) 160mm dlameter m 638 5.1.6 Extra over item 8.3.1 for the supplying, laying and bedding of specials complete with couplings 6.2.2 (Fittings of PVC pipes, Cast Iron or Aluminium) 5,2.0 Bends 22,5 degree bends 1355.65 289.65 868.95 741.60 2 224.80 451.95 No 3 5.2.1 a) 63mm 312.00 753.76 753.76 441.76 441.76 312.00 5.2.2 b) 90mm Νo 1 658,65 1 317,29 657.40 987.35 1 974.69 329.70 c) 160mm No 2 5.2.3 45 degree bends 789.76 789.76 0 5.2.4 aj 110mm No b) 160mm No 0 5.2.5 90 degree bends 171012 492.32 984.64 362.74 725.48 855.06 No 5.2.6 a) 63mm 2 475.94 379.12 475.94 855.08 855.06 b) 90mm No 1 379.12 5.2.7 1 394.99 394.99 1 268,77 1 268.77 873.78 673.78 No 5,2,8 c) 160mm 5.3.0 Saddles and uPVC pipes tees 90.35 903.50 23.65 238.50 114 1 140.00 a) 75 x 32 reducing tee

1 156 045 84

1 246 678.64

90 632.81

TOTAL CARRIED FORWARD

| CONTRACT NO::04/2018 A- KALOSI TRADING PROJECTS | | | | | | | | | | |
|---|-------------|--|------|-----|----------|--------------|----------|------------------------|--------------|---------------------|
| | | | Unit | Qty | Rate | Amount | Rafe | Amount 1 246 678.64 | Rate | Amount 90 632.81 |
| TOTAL | BROUGHT F | ORWARD | | | | 1 156 045,84 | | 1 236 6/8364 | | 20 037.01 |
| 5.3.2 | | b) 62 x 32 reducing tee | No | 3 | 19.27 | 57.81 • | 300 | 900,000 | 280.73 | 842.19 |
| 5.3.3 | | c) 90 x 32mm reducing saddles | No | 18 | 7.29 | 131.22 | 342 | 6 156.00 | 334.71 | 6 024.78 |
| 5.3.4 | | d) 90 x 75mm reducing tee | No | 2 | 32.15 | 64.30 | 372 | 744.00 | 339.85 | 679.70 |
| 5.3.5 | | e) 160 x 32mm reducing saddle | No | 2 | 124.31 | 248.62 | 1000 | 2 000.00 | 875.69 | 1 751.38 |
| 5.3.6 | | f) 160 x 75mm reducing tee | No | 4 | 176.25 | 705.00 | 1000 | 4 000,00 | 823,75 | 3 295.00 |
| 5.3.7 | | g) 160mm equal tee | Νo | 2 | 461,70 | 923.40 | 646 | 1 292.40 | 184.50 | 369.00 |
| 5.3.8 | | h) 160 x 110mm reducing tee | No | 2 | 301.00 | 602.00 | 1260 | 2 520.00 | 959,00 | 1 918.00 |
| 5.40 | | Reducers | | | | | | | | • |
| | | Flanged Adaptor CI for use with uPVC pipes | | | | | | | | : |
| 5.4.1 | | a) 32 x 25mm | No | 90 | 14.00 | 1 260,00 | 103 | 9 180.00 | 00.88 | 7 920.00 |
| 5,4.2 | | b) 160 x 110mm | No | 1 | 1 191.10 | 1 191.10 | 1191 | 1 191.10 | : | - |
| 5.5.0 | | VALVES | | | | - | | | | |
| | 8.2.3 | Extra-over on item 8.2.1 for the supplying, handle, lay, bed of valves with couplings in valve box. Complete with cutting of pipes and valve testing. Cl gate to SANS 0664, Class 10, ends socketted for uPVC pipes to SANS 0996, non-rising spindle, LH closing | | | | | | | T Management | |
| 5,5,1 | | a) 110mm | No | 4 | 301.00 | 1 204.00 | 3140 | 12 560.00 | 2 839.00 | 11 356.00 |
| | | Anchor/thrust blocks and pedestals: | | | | | | | : | |
| | | Concrete: | | | | 1 : | | | | • |
| 5.5.3 | | Class . (15) MPa/19 mm | m³ | 25 | 27.82 | 695.50 | 1650 | 11 250.00 | 1 622,18 | 40 554,50 |
| 5.6.0 | | CHAMDERS | | | | | | | • | |
| 5,6,1 | | Valves and hydrant chambers complete with step irons, cover and frames as per applicable drawing, up to 1.5m depth. | No | 2 | 2 974.00 | 5 949.00 | 3060 | 6 120.00 | 86,00 | 172.00 |
| 5.6.2 | PSLO-6 | yard connection complete with apron and soak away and plastic taps (refer to drawing NO 60113- W-DY-07 Rev 0) | No | 90 | 225,00 | 20 250.00 | 1140 | 102 600,00 | 915.00 | 82 350.00 |
| TOTAL | L CARRIED I | ORWARD TO SUMMARY | | | <u> </u> | 1 189 326.79 | <u> </u> | 1 437 192 14 | | 247 865.36 |

| SUMMARY | ···[| TENDERED AMOUNT | New tender rates | Difference in tendered amount |
|------------------------------------|------|-----------------|------------------|-------------------------------|
| Schedule 1: PRELIMINARY AND GENERA | | 576 852.20 | 687 324.00 | 110 471.80 |
| Schedule 2: HANI PARK X20 | | } | 1 437 192.14 | 247 865.36 |
| SUB-TOTAL 1 | | 1 766 178,99 | 2 124 516.14 | |
| CONTINGENCIES (10%) | | 176 617.90 | 212 451.61 | 35 833.72 |
| TOTAL CONSTRUCTION BUDGET | | 1 942 796.86 | | 394 170.87 |